MYSORE DIVISION.

Dated 8th September 1916.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 20th October 1916, for restoring the Honganahalli (Kommerahalli) Tank, Registered No. 15 of Mandya Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1917.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Honganahalli, (Kommerahalli) Tank, Registered No. 15 of Mandya Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate for restoring Honganahalli, (Kommerahalli) Tank, Registered No. 15 of Mandya Taluk.

No.	Items of work	Per	Quantity
	Bund.		
1	Earthwork including watering and tamping	C. yd.	14,143
2	Turfing	Sq.	1,550·08
3	Dismantling and resetting old stone work with new jelly	C. yd.	1,615
4	New rough stone revetment	,,	1,854
5	Gravel backing	,,	551
6	Grade stones	Each	51
7	Index stones	,,	51
8	B. M. stones	,,	2
9	Registered number stone	,,	1
10	Date stone	,,	1
	Right waste weir.		
1	Soft rock excavation	C. yd.	548
2	Gravelly soil	,,	209
3	Dismantling brick work	C. ft.	152
4	Brick in surki mortar	,,	2,050
5	Burnt stone slabs, dressed	,,	188
6	Removing and resetting old slabs including dressing	,,	63
7	Plastering with surki mortar	Sq.	17·81
8	New stone work	C. yd.	128
9	Jelly wedging to apron	L. S. Rs.	
10	Old stone work	C. yd.	15
	Supply feeder channel.		
1	Earthwork	C. yd.	2,084
2	Turfing	Sq.	212·64
3	New rough stone work waste weir with under sluice	C. yd.	100
4	Earthwork	,,	111
5	Brick in mortar	C. ft.	857
6	Burnt stone slabs	,,	67
7	Plastering with surki mortar	Sq.	5·01
8	New rough stone work	C. yd.	103
9	Draft cutting	,,	176
	Repairing the tunnel of 4 vents 3½ to 6½.		
1	Dismantling brick work	C. ft.	156
2	Removing rough stone slabs	S. ft.	215
3	Brick in chunam	C. ft.	234
4	Plastering with chunam	Sq.	12·72
5	Guard stones	No.	4
6	Burnt stone slabs ordinary	C. ft.	108
7	Earthwork to approach	C. yd.	30
8	Metalling and gravelling	,,	3
9	Old stone work	,,	16

Dated 11th September 1916.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 10th October 1916, for restoring Kanagal Hirikere and Kannikere, Registered No. 371 of Hunsur Taluk, Mysore District. An approximate estimate of quantities are given below. These quantities are not guaranteed. The work should be completed by the end of January 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for restoring Kanagal Hirikere and Kannikere, Registered No. 371 of Hunsur Taluk, Mysore District," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate for restoring Kanagal Hirikere and Kannikere, Registered No. 371 of Hunsur Taluk, Mysore District.

No	Items of work	Per	Quantity
	Bund		
1	Earthwork, cody earth to be used only lead allowed	C. yd.	3,091
2	Turfing	S. yd.	2,351
3	Earthwork including watering and tamping	C. yd	3,371
4	Clearing silt in breach	,,	500
5	Puddle wall	C. ft.	9,837
6	Earthwork excavating for foundation of puddle wall	C. yd.	142
7	Turfing	S. yd.	410
8	Fixing new grade stones	Each	31
9	Fixing gauge stone	,,	1
10	Fixing Registered No. stone	,,	1
11	Rough stone work, new	C. yd.	846
12	Do old	,,	41
13	Gravel backing	,,	169
14	Fixing B. M. stones	Each	2
15	Earthwork excavation	C. yd.	180
	Waste Weirs.		
1	Burnt brick in surki mortar	C. ft.	1,542
2	Burnt stone slabs	S. ft.	197
3	Plastering with surki-mortar	Sq.	9·67
4	Filling jelly to crevices and with stones	C. yd.	158
5	Rough stone work, new	,,	52
6	Do old	,,	12
7	Earthwork	,,	3,353
8	Concrete in surki mortar	C. ft.	303
9	Burnt brick in surki mortar	,,	1,182
10	Burnt stone slabs	S. ft.	415
11	Plastering with surki mortar	S. yd.	11·03
12	Rough stone work new	C. yd.	141
13	Do old	,,	61

Notice dated 5th September 1916.

The public are hereby informed that a portion of French Rocks Station-Nelligere road in the 12th mile between the Honakere bridge and Honakere village is closed for the traffic since the road is washed away during the heavy rains in the last week of August. The traffic will have to go in the old road crossing the river where it is not bridged.

Y. ASVATHANARAYANA RAO,
Executive Engineer.